

कार्यालय प्रभारी परिसम्पत्ति
वानिकी महाविद्यालय, रानीचौरी, टिहरी गढ़वाल

पत्रांक:- वा0म0/परि0/ 1460/L

दिनांक 02.05.2025

कार्यालय ज्ञाप

कृपया अवगत कराना है कि वानिकी महाविद्यालय, रानीचौरी के नये भागीरथी छात्रावास में नये लोहे का मेन गेट बनाने का कार्य करवाया जाना है। कार्य की अनुमानित लागत रु0 73,400.00 (रु0 तिहत्तर हजार, चार सौ मात्र) हैं।

उक्त कार्य को करवाने हेतु सरकारी विभागों में पंजीकृत ठेकेदारों/फर्मों से कोटेशन प्राप्त किये जा रहे हैं। इच्छुक ठेकेदार/फर्म कोटेशन किसी भी कार्य दिवस में अधोहस्ताक्षरी कार्यालय एवं विश्वविद्यालय की website uuhf.ac.in के Tender/Quotation पर कार्य की सूचना प्राप्त कर सकते हैं। प्राप्त सभी कोटेशन दिनांक 15.05.2025 को समिति सदस्यों के सम्मुख खोली जायेंगी।

अतः इच्छुक ठेकेदार/फर्म कार्य हेतु अपने कोटेशन दिनांक 14.05.2025 तक पंजीकृत डाक द्वारा अधोहस्ताक्षरी कार्यालय को भेजना सुनिश्चित करने का कष्ट करें। उक्त समय के बाद प्राप्त कोटेशन पर विचार नहीं किया जायेगा।

नियम एवं शर्तें:-


1. प्राप्त कोटेशनों में भवन निर्माण कार्यों के अन्तर्गत पंजीकृत ठेकेदार/फर्म को प्राथमिकता दी जायेगी।
2. कोटेशन अपने Printed Letter Head पर देना होगा, जिसमें उनका नाम, पता, फोन नं०, GST No., PAN No. आदि जानकारी अंकित की जानी अनिवार्य होगी।
3. सभी कोटेशन रजिस्टर्ड डाक द्वारा प्राप्त की जायेगी। कोटेशन By hand नहीं ली जायेंगी।
4. सभी कोटेशन संलग्न प्रारूप में भरकर देने होंगे।
5. कार्य का नाम लिफाफे के बाहर भी लिखा होना अनिवार्य है।

/

प्रभारी परिसम्पत्ति

प्रतिलिपि:-

1. अधिष्ठाता, वानिकी महाविद्यालय, रानीचौरी को सादर सूचनार्थ।
2. लेखाधिकारी, वानिकी महाविद्यालय, रानीचौरी को सूचनार्थ।
3. प्रभारी अधिकारी, संगणक केन्द्र, वानिकी महाविद्यालय, रानीचौरी को website पर अपलोड करने हेतु।
5. अवर अभियन्ता (सि०)/सहायक निदेशक (सि०) को आवश्यक कार्यवाही हेतु।
6. समस्त सूचना पट्टों पर।


21/05/25
प्रभारी परिसम्पत्ति

Bill Of Quantity DSR 2023

Name of work:- Construction of New Iron main gate in the new Bhagirathi hostel COF Ranichauri

S.N	DSR 2023	Item of Work	Quantity	Unit	Rate	Amount
1	2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	1.52	cum		
2	4.1.5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size)	0.28	cum		
3	6.1.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:4 (1 cement : 4 coarse sand)	0.71	cum		
4	6.4.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:4 (1 cement : 4 coarse sand)	2.53	cum		
5	13.1.1	CEMENT PLASTER (IN FINE SAND) 12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	22.56	sqm		
6	10.25.2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	199.02	k.g		